



BUILDING CORPORATION

First Choice For Facilities Renovation & Construction

**COSA JOC
Cost Proposal**

Date: 12-21-07

Owner: City of San Antonio

Project Manager: Bill Pennell

ALPHA No.: 113-061

Description: BONNIE CONNER PARK, PHASE II
7038 HAUSMAN Rd.

BASE BID

Inclusions:

1. Layout roadway, parking lot, and play ground area as per plans.
2. Excavate, place select fill and compact as per plans.
3. Install machine formed curbing as per plans.
4. Form and place concrete sidewalks and area around play ground.
5. Place and stripe roadway and parking lot.
6. Install owner furnished drinking fountain.
7. Install water line to drinking fountain and drain line to dry well as per plans.
8. Install owner furnished Pavilion as per plans and manufacturer recommendations.
9. Install owner furnished Play Ground Equipment as per plans and manufacturer recommendations.
10. Install (2 ea.) 4" conduits at each end of parking lot as per plans.
11. Install 28" x 20 " Architectural Pipe drain at entrance of park.

Performance Time:

Approximately 90 days from NTP

436 Breesport St., San Antonio, Texas 78216

V 210-767-0955 F 210-767-0956 www.alphabuilding.com

CREATING ENVIRONMENTS WHERE GREAT THINGS CAN HAPPEN

ALTERNATE BID #1

Inclusions:

1. Install 6ea. Picnic Tables as per plans.

ALTERNATE BID #2

1. Install 6ea. Park Benches as per plans.


Exclusions:

1. No handling of Hazardous Materials of any kind.
2. No non-standard or over time work.
3. No architectural, electrical, mechanical or plumbing other than that shown on drawings.

Total Base bid (breakout attached).....\$ 302,626.32
Total Alternate Bid #1 (breakout attached).....\$ 4,822.43
Total Alternate Bid #2 (breakout attached).....\$ 4,344.57
Total Project cost..... \$ 311,793.32

Sincerely,

Alpha Building Corporation



Robert S. Crow
Project Manager

Attachments: JOCWorks Estimate Detail



BUILDING CORPORATION

First Choice for Facilities Renovation & Construction

Estimate Details
Labor - Material - Equipment
Gary Haverly
Alpha Building Corporation
City of San Antonio - COSA - Job Order Contract

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

Division Summary (MF04)

01 - General Requirements	\$96,962.77	23 - Heating, Ventilating, and Air-Conditioning (HVAC)	
02 - Existing Conditions		26 - Electrical	
03 - Concrete	\$70,418.09	27 - Communications	
04 - Masonry		28 - Electronic Safety and Security	
05 - Metals	\$800.40	31 - Earthwork	\$725.40
06 - Wood, Plastics, and Composites		32 - Exterior Improvements	\$157,708.42
07 - Thermal and Moisture Protection		33 - Utilities	\$3,249.00
08 - Openings		34 - Transportation	
09 - Finishes		35 - Waterway and Marine Transportation	
10 - Specialties	\$377.00	41 - Material Processing and Handling Equipment	
11 - Equipment		44 - Pollution Control Equipment	
12 - Furnishings		48 - Electric Power Generation	\$78,782.88
13 - Special Construction		Alternates	
14 - Conveying Equipment		Trades	
21 - Fire Suppression		Assemblies	
22 - Plumbing	\$9,526.00	MF04 Bare Total (Without totalling components)	\$418,549.96
Totalling Components			
07 - COSA JOC Standard (-20.4000%)	\$69,673.77	07 - Non-Priced Line Items Multiplier (10.0000%)	\$7,701.19
07 - Priced Line Items	\$341,538.08	02 - 07 RS Means CCI San Antonio, TX 1 (-15.7965%)	\$(63,951.06)
07 - Non-Priced Line Items	\$77,011.88		

Material, Labor, and Equipment Totals (No Totalling Components)

	Bare Cost
Material:	\$190,948.08
Labor:	\$93,868.88
Equipment:	\$71,589.85
Other:	\$62,343.15
Labourours:	1,199.28

Grand Total \$302,626.32

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
01 - General Requirements									
1	01-31-13-90-0020 Performance bond, for buildings, minimum	Job		309,586.39	0.00	0.00	0.00	0.6000%	\$1,857.52
2	01-31-13-90-0100 Performance bond, for buildings, minimum	Job		309,586.39	0.00	0.00	0.00	2.5000%	\$7,739.66
3	01-41-26-50-0100 Permits, rule of thumb, most cities, maximum	Job		305,685.62	0.00	0.00	0.00	2.0000%	\$6,113.71
4	01-45-23-50-0200 Testing and inspecting services, asphalt testing, compressive strength Marshall stability, set of 3	Ea.		3.00	0.00	0.00	0.00	\$165.00	\$495.00
5	01-45-23-50-1800 Testing and inspecting services, concrete testing, compressive test, cylinder, ASTM C 39, delivered to lab	Ea.		6.00	0.00	0.00	0.00	\$13.00	\$78.00
6	01-45-23-50-1950 Testing and inspecting services, concrete testing, compressive test, cylinder, ASTM C 39, picked up by lab, average	Ea.		6.00	0.00	0.00	0.00	\$20.00	\$120.00
7	01-45-23-50-4740 Testing and inspecting services, soil testing, soil density, sand cone method ASTM D1556	Ea.		3.00	0.00	0.00	0.00	\$30.17	\$90.51
8	01-45-23-50-5550 Testing and inspecting services, technician for inspection, per day, earthwork	Ea.		2.00	0.00	0.00	0.00	\$231.00	\$462.00
9	01-54-33-20-0095-2 Day/Earthwork equipment rental, without operators, auger, for fence posts, gas engine, hand held	Ea.		1.00	0.00	0.00	4.67	\$4.67	\$4.67
10	01-54-33-20-0600-2 Day/Earthwork equipment rental, without operators, brush chipper, gas engine, 15" cutter head, 165 H.P.	Ea.		5.00	0.00	0.00	165.00	\$165.00	\$825.00
11	01-54-33-20-1910-4 Month:Earthwork equipment rental, without operators, grader, self-propelled, 30,000 lb.	Ea.		1.00	0.00	0.00	4,575.00	\$4,575.00	\$4,575.00
12	01-54-33-20-2800-2 Day/Earthwork equipment rental, without operators, log chipper, up to 22" diameter, 600 H.P.	Ea.		5.00	0.00	0.00	430.00	\$430.00	\$2,150.00
13	01-54-33-20-2900-2 Day/Earthwork equipment rental, without operators, rake, spring tooth, with tractor	Ea.		5.00	0.00	0.00	219.00	\$219.00	\$1,095.00
14	01-54-33-20-3170-2 Day/Earthwork equipment rental, without operators, landfill compactor, 220 HP	Ea.		5.00	0.00	0.00	1,225.00	\$1,225.00	\$6,125.00
15	01-54-33-20-3300-2 Day/Earthwork equipment rental, without	Ea.		5.00	0.00	0.00	925.00	\$925.00	\$4,625.00

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

01 - General Requirements

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
16	01-54-33-20-3600-2 operators, sheepfoot vibratory roller, 200 H.P. Day/Earthwork equipment rental, without operators, scrapers, self-propelled, 4 x 4 drive, 2 engine, 24 C.Y. capacity	Ea.		5.00	0.00	0.00	2,425.00	\$2,425.00	\$12,125.00
17	01-54-33-20-4310-2 Day/Earthwork equipment rental, without operators, tractor, crawler, with bulldozer, torque converter, diesel 300 H.P.	Ea.		5.00	0.00	0.00	1,375.00	\$1,375.00	\$6,875.00
18	01-54-33-20-4730-2 Day/Earthwork equipment rental, without operators, tractor loader, wheel, torque converter, 4 x 4, 3 to 4-1/2 C.Y., 170 H.P.	Ea.		5.00	0.00	0.00	490.00	\$490.00	\$2,450.00
19	01-54-33-20-5200-2 Day/Earthwork equipment rental, without operators, trencher, chain type, diesel, 8' deep, 16' wide	Ea.		2.00	0.00	0.00	1,825.00	\$1,825.00	\$3,650.00
20	01-54-33-20-5300-2 Day/Earthwork equipment rental, without operators, truck, dump, three axle dump, 16 ton, 12 C.Y. payload	Ea.		5.00	0.00	0.00	435.00	\$435.00	\$2,175.00
21	01-54-36-50-0100 Mobilization or demobilization, up to 25 mile haul distance, 50 miles round trip for mobilization/demobilization crew, dozer, loader, backhoe, excavator, grader, paver, roller, above 150 H.P. dozer, loader, backhoe, grader, paver, roller, Curb Equio	Ea.	B-34K	14.00	0.00	79.00	192.00	\$340.00	\$4,760.00
22	01-54-36-50-0100-2500 Mobilization or demobilization, for each additional 5 miles haul distance, add	Ea.	B-34K	14.00	0.00	7.90	19.20	\$27.10	\$379.40
23	01-54-36-50-0600 Mobilization or demobilization, up to 25 mile haul distance, 50 miles round trip for mobilization/demobilization crew, scraper, self-propelled scraper, 15 C.Y. Scraper	Ea.	B-34K	2.00	0.00	94.50	231.00	\$410.00	\$820.00
24	01-54-36-50-0600-2500 Mobilization or demobilization, for each additional 5 miles haul distance, add	Ea.	B-34K	2.00	0.00	9.45	23.10	\$32.55	\$65.10
25	01-54-36-50-1150 Mobilization or demobilization, up to 25 mile haul distance, 50 miles round trip for mobilization/demobilization crew, small equipment, equipment up to 70 HP, on flatbed trailer behind pickup truck Fencing, streeps foot	Ea.	A-03D	4.00	0.00	57.00	46.00	\$145.00	\$580.00

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

01 - General Requirements

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
26	01-54-36-50-1150-2500 Mobilization or demobilization, for each additional 5 miles haul distance, add	Ea.	A-03D	4.00	0.00	5.70	4.60	\$10.30	\$41.20
27	01-56-26-50-0100 Temporary fencing, chain link, 11 gauge, 6' high	L.F.	2 CLAB	2,300.00	6.50	1.53	0.00	\$9.70	\$22,310.00
28	01-71-23-13-1400 Construction layout, crew for roadway layout, 4 person crew	Day	A-08	2.00	0.00	1,250.00	58.00	\$2,100.00	\$4,200.00
29	01-71-23-19-0150 Surveyor stakes, hardwood, 2" x 2" x 24" long	C		2.00	80.00	0.00	0.00	\$88.00	\$176.00

01 - General Requirements Total

\$96,962.77

03 - Concrete

30	03-11-13-35-7500 Forms in place, elevated slabs, includes shoring, erecting, bracing, stripping and cleaning, depressed area forms, to 12" high, 4 use	L.F.	C-01	80.00	0.74	3.70	0.00	\$6.95	\$556.00
31	03-11-13-65-2000 Forms in place, slab on grade, includes erecting, bracing, stripping and cleaning, curb forms, wood, 6" to 12" high, on grade, 1 use	SFCA	C-01	926.00	1.95	5.15	0.00	\$10.70	\$9,908.20
32	03-21-05-10-1206 Rebar accessories, for reinforcing steel, high chairs, individual, no plates (1 HC), to 3" high, plastic	C		9.60	108.00	0.00	0.00	\$119.00	\$1,142.40
33	03-21-10-60-0602 Reinforcing in place, A615 Grade 60, including accessories labor, excluding material for accessories, slab on grade, #3 to #7	Lb.	4 RODM	11,505.00	0.45	0.31	0.00	\$1.03	\$11,850.15
34	03-21-10-60-0602-2000 Reinforcing in place A615, for unloading & sorting, add to above	Ton	4 RODM	5.75	0.00	22.50	7.40	\$46.00	\$264.50
35	03-21-10-60-0602-2210 Reinforcing in place A615, for crane cost for handling, add to above, average	Ton	4 RODM	5.75	0.00	24.50	8.05	\$50.00	\$287.50
36	03-21-10-60-2420 Reinforcing in place, A615 Grade 60, dowels, 2 feet long, deformed, #5 To hold bumpers in place	Ea.	2 RODM	80.00	1.03	1.52	0.00	\$3.73	\$298.40
37	03-31-05-35-0150 Normal weight concrete, ready mix, includes local aggregate, sand, portland cement, and water, excludes all additives and treatments, 3000 psi	C.Y.		247.00	104.00	0.00	0.00	\$114.00	\$28,158.00
38	03-31-05-35-0150 Normal weight concrete, ready mix, includes local aggregate, sand, portland cement, and water,	C.Y.		23.00	104.00	0.00	0.00	\$114.00	\$2,622.00

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

03 - Concrete

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
excludes all additives and treatments, 3000 psi For mounting Play-ground equipment									
39	03-31-05-70-4350 Placing concrete, includes labor and equipment to place and vibrate, slab on grade, 4" thick, pumped	C.Y.	C-20	247.00	0.00	15.30	5.80	\$31.50	\$7,780.50
40	03-31-05-70-4350 Placing concrete, includes labor and equipment to place and vibrate, slab on grade, 4" thick, pumped For Play-ground Equipment	C.Y.	C-20	23.00	0.00	15.30	5.80	\$31.50	\$724.50
41	03-35-29-30-0150 Finishing floors, monolithic, screed, float, and broom finish	S.F.	1 CEF1	9,614.00	0.00	0.45	0.00	\$0.71	\$6,825.94

03 - Concrete Total

\$70,418.09

05 - Metals

42	05-05-23-05-0300 Anchor bolts, L-type, including hex nut and washer, 3/4" diameter x 12" long	Ea.	2 CARP	24.00	1.51	13.05	0.00	\$23.00	\$552.00
43	05-12-23-77-4400 Structural steel projects, A992 steel, shop fabricated for 100-ton, 1-2 story project, including bolted connections and shop primer, column base plates, heavy, over 150 lb	Lb.	E-02	120.00	1.18	0.30	0.21	\$2.07	\$248.40

05 - Metals Total

\$800.40

10 - Specialties

44	10-14-53-20-0100 Traffic signs, stock, excluding posts, .080" aluminum, 24" x 24", high intensity STOP SIGN	Ea.	B-80	1.00	59.50	14.30	8.00	\$98.00	\$98.00
45	10-14-53-20-0100-1500 Traffic signs, add to above for steel posts, galvanized, 10'-0" upright, bolted	Ea.	B-80	3.00	19.30	5.00	2.80	\$32.00	\$96.00
46	10-14-53-20-1300 Traffic signs, guide and directional signs, 24" x 24", stock signs, high intensity HANDICAP PARKING SIGNS	Ea.	B-80	2.00	53.50	14.30	8.00	\$91.50	\$183.00

10 - Specialties Total

\$377.00

22 - Plumbing

47	22-05-23-20-1470 Valves, bronze, ball, 150 psi, threaded, 1"	Ea.	1 PLUM	1.00	19.85	18.85	0.00	\$51.50	\$51.50
48	22-05-76-10-0120 Cleanouts, floor type, round or square, scoriated	Ea.	1 PLUM	1.00	168.00	45.00	0.00	\$255.00	\$255.00

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

22 - Plumbing

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
49	22-05-76-20-5110 nickel bronze top, 3" pipe size Cleanout tees, plastic, tees and adapters, PVC, DWV, cleanout plug, 3" pipe size	Ea.	Q-01	1.00	3.03	17.90	0.00	\$31.50	\$31.50
50	22-05-76-20-5190 Cleanout tees, plastic, tees and adapters, PVC, DWV, cleanout adapter fitting, 3" pipe size	Ea.	Q-01	1.00	7.40	17.90	0.00	\$36.00	\$36.00
51	22-11-13-74-1880 Pipe, plastic, including couplings 10' O.C., and hangers 3 per 10', PVC, schedule 40, 1" diameter	L.F.	1 PLUM	80.00	1.47	7.80	0.00	\$13.70	\$1,096.00
52	22-11-13-74-1910 Pipe, plastic, including couplings 10' O.C., and hangers 3 per 10', PVC, schedule 40, 2" diameter	L.F.	Q-01	6.00	2.75	10.95	0.00	\$20.00	\$120.00
53	22-11-13-74-1930 Pipe, plastic, including couplings 10' O.C., and hangers 3 per 10', PVC, schedule 40, 3" diameter	L.F.	Q-01	80.00	5.15	12.20	0.00	\$24.50	\$1,960.00
54	22-11-13-74-1940 Pipe, plastic, including couplings 10' O.C., and hangers 3 per 10', PVC, schedule 40, 4" diameter	L.F.	Q-01	180.00	6.85	13.45	0.00	\$28.50	\$5,130.00
55	22-11-13-76-2780 Pipe, plastic, fittings, PVC, white, schedule 40, socket joints, 90° elbow, 1"	Ea.	1 PLUM	1.00	0.66	14.35	0.00	\$23.00	\$23.00
56	22-11-13-76-3250 Pipe, plastic, fittings, PVC, white, schedule 40, socket joints, tee, 3"	Ea.	Q-01	1.00	10.50	42.50	0.00	\$77.50	\$77.50
57	22-11-13-76-5114 Pipe, plastic, fittings, DWV, PVC, schedule 40, socket joints, 1/4 bend, long sweep, 3"	Ea.	Q-01	2.00	10.40	31.00	0.00	\$59.50	\$119.00
58	22-11-13-76-5412 Pipe, plastic, fittings, DWV, PVC, schedule 40, socket joints, reducer bushing, 3" x 1-1/2"	Ea.	Q-01	2.00	7.10	23.50	0.00	\$44.50	\$89.00
59	22-11-13-76-8150 Pipe, plastic, fittings, polybutyl or polyethyl pipe, compression type, PVC, including insert stiffeners, 160 psi cold water, male adapter, 1" MPT x 1" CTS	Ea.	1 PLUM	3.00	3.93	17.90	0.00	\$32.50	\$97.50
60	22-47-13-10-9860-9980 Drinking fountains, for rough-in, supply and waste, add	Ea.	1 PLUM	1.00	121.00	196.00	0.00	\$440.00	\$440.00

22 - Plumbing Total

\$9,526.00

31 - Earthwork

61	31-25-13-10-1100 Synthetic erosion control, silt fence, polypropylene, 3' high, adverse conditions	L.F.	2 CLAB	620.00	0.34	0.48	0.00	\$1.17	\$725.40
----	--	------	--------	--------	------	------	------	--------	----------

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

31 - Earthwork

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
31 - Earthwork Total									\$725.40

32 - Exterior Improvements

62	32-11-23-23-1513	Base course drainage layers, for roadways and large paved areas, alternate method to figure base course, crushed 3/4" stone base, compacted, 12" deep	E.C.Y.	B-36B	1,770.00	32.00	1.55	2.35	\$40.00	\$70,800.00
63	32-11-23-23-1513-6900	Base course drainage layers, for small and irregular areas, add	E.C.Y.	B-36B	1,770.00	0.00	0.78	1.18	\$1.95	\$3,451.50
64	32-12-16-13-0340	Plant-mix asphalt paving, for highways and large paved areas, excluding hauling costs, wearing course, 1-1/2" thick	S.Y.	B-25B	2,580.00	3.94	0.40	0.32	\$5.35	\$13,803.00
65	32-12-16-14-0020	Asphaltic concrete pavement, lots and driveways, 6" stone base, 2" binder course, 1" topping	S.F.	B-25C	23,216.00	1.73	0.17	0.22	\$2.42	\$56,182.72
66	32-16-13-13-0415	Cast in place concrete curbs and gutters, concrete, machine formed, 6" x 18", straight	L.F.	B-69A	447.00	3.80	0.76	0.34	\$5.80	\$2,592.60
67	32-16-13-13-0416	Cast in place concrete curbs and gutters, concrete, machine formed, 6" x 18", radius	L.F.	B-69A	963.00	3.96	1.70	0.76	\$7.95	\$7,576.35
68	32-17-13-19-1000	Precast concrete parking bumpers, wheel stops, including 2 dowels per each, precast concrete, 6" x 10" x 6'-0"	Ea.	B-02	40.00	46.50	9.70	0.00	\$67.00	\$2,680.00
69	32-17-23-13-0020	Painted pavement markings, acrylic waterborne, white or yellow, 4" wide	L.F.	B-78	1,207.00	0.19	0.07	0.02	\$0.35	\$422.45
70	32-17-23-13-0600	Painted pavement markings, acrylic waterborne, white or yellow, 12" wide	L.F.	B-78	12.50	0.46	0.35	0.10	\$1.19	\$14.88
71	32-17-23-14-0790	Pavement markings, layout of pavement marking	L.F.	A-02	1,232.00	0.00	0.03	0.01	\$0.06	\$73.92
72	32-17-23-14-1200	Pavement markings, handicap symbol	Ea.	2 PORD	2.00	31.50	13.10	0.00	\$55.50	\$111.00
32 - Exterior Improvements Total										\$157,708.42

33 - Utilities

73	33-42-16-15-3060	Oval arch culverts, excluding excavation and backfill, corrugated galvanized or aluminum, coated and paved, 28" x 20", 14 gauge, 24'	L.F.	B-14	38.00	58.00	11.70	1.95	\$85.50	\$3,249.00
----	------------------	--	------	------	-------	-------	-------	------	---------	------------

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

33 - Utilities

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
equivalent									
33 - Utilities Total									\$3,249.00
Alternates									
74	01-11-31-10-0060	Architectural fees, for new construction, minimum	Project	304.179.93	0.00	0.00	0.00	0.4500%	\$1,368.81
75	01-54-33-20-0095-1	Hourly:Earthwork equipment rental, without operators, auger, for fence posts, gas engine, hand held	Hr.	8.00	0.04	124.30	0.00	\$124.34	\$994.72
RS Menas has \$62.15 per person x 2 men. It takes two men to operate this equipment									
76	01-54-33-20-1910-1	Hourly:Earthwork equipment rental, without operators, grader, self-propelled, 30,000 lb. 4 weeks of grading	Hr.	160.00	25.05	63.15	0.00	\$88.20	\$14,112.00
77	01-54-33-20-2900-1	Hourly:Earthwork equipment rental, without operators, rake, spring tooth, with tractor Raking the work are and laydown area getting it ready for final soil and sodi	Hr.	40.00	8.04	60.55	0.00	\$68.59	\$2,743.60
78	01-54-33-20-3170-1	Hourly:Earthwork equipment rental, without operators, landfill compactor, 220 HP Rolling the sub base and compacting it for pre for the final base for the asphalt	Hr.	40.00	62.00	60.55	0.00	\$122.55	\$4,902.00
79	01-54-33-20-3300-1	Hourly:Earthwork equipment rental, without operators, sheepfoot vibratory roller, 200 H.P. Working the base area for the curbs	Hr.	40.00	50.15	62.15	0.00	\$112.30	\$4,492.00
80	01-54-33-20-3600-1	Hourly:Earthwork equipment rental, without operators, scrapers, self-propelled, 4 x 4 drive, 2 engine, 24 C.Y. capacity Scraping the driveway and the parking area	Hr.	40.00	137.50	63.15	0.00	\$200.65	\$8,026.00
81	01-54-33-20-4310-1	Hourly:Earthwork equipment rental, without operators, tractor, crawler, with bulldozer, torque converter, diesel 300 H.P. Clearing the work area and the larger cut's	Hr.	40.00	59.75	63.15	0.00	\$122.90	\$4,916.00
82	01-54-33-20-4730-1	Hourly:Earthwork equipment rental, without operators, tractor loader, wheel, torque converter, 4 x 4, 3 to 4-1/2 C.Y., 170 H.P. Loading the clipped mulching and the rubbish out and loading the trucks out	Hr.	40.00	24.25	63.15	0.00	\$87.40	\$3,486.00
83	01-54-33-20-5200-1	Hourly:Earthwork equipment rental, without operators, trencher, chain type, diesel, 8' deep, 16" wide	Hr.	16.00	63.00	63.15	0.00	\$126.15	\$2,018.40

Estimate Details

Estimator: Gary Haverly

BONNIE CONNER PARK PHASE II

Alternates

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total
Trenching the drain lines in									
84	01-54-33-20-5300-1 Hourly:Earthwork equipment rental, without operators, truck, dump, three axle dump, 16 ton, 12 C.Y. payload Trucking all the rubbish out to the land fill	Hr.		40.00	33.50	48.60	0.00	\$82.10	\$3,284.00
85	01-56-26-50-0100 Demo - Temporary fencing, chain link, 11 gauge, L.F. 6' high Original Values (M:\$6.50 L:\$1.53 E: 0:300.00 LH:0.053) Labor Adjustment 50% (\$0.7700)	L.F.	2 CLAB	2,300.00	0.00	0.77	0.00	\$0.77	\$1,771.00
Removing the fencing after the project is completed									
86	11-68-13-20-0190 Modular playground, basic components, steps, deck-to-deck, three 8" steps LABOR ONLY TO INSTALL PLAY GROUND EQUIPMENT	HR	B-01	160.00	0.00	62.15	0.00	\$62.15	\$9,944.00
87	13-34-19-50-0200 Pre engineered steel buildings, clear span rigid frame, 30 P.S.F. roof and 20 P.S.F. wind load, excluding footings, slabs and anchor bolts, 26 gauge colored roofing and siding, 30' to 40' wide, 10' eave height	SF Flr.	E-02	2,115.00	0.00	4.22	2.89	\$7.11	\$15,037.65
88	32-16-13-13-0415 Cast in place concrete curbs and gutters, concrete, machine formed, 6" x 18" straight Extral labor for saw-tooth curbing	L.F.	B-69A	405.00	0.00	3.80	0.34	\$4.14	\$1,676.70
Alternates Total									\$78,782.88

Estimate Grand Total 302,626.32



Estimate Details
 Labor - Material - Equipment
 Gary Haverly
 Alpha Building Corporation
 City of San Antonio - COSA - Job Order Contract

ADD ALTERNATE #1: 6 PICNIC TABLES

Figure 1. The effect of the number of trials on the number of correct responses. The number of correct responses was significantly higher than the number of incorrect responses in all cases. Error bars represent the standard error of the mean.

Material:	\$4,080.00
Labor:	\$219.00
Equipment:	\$0.00
Other:	\$146.59
Labourhours:	0.00

BONNIE CONNER PARK PHASE II - 113-061

Estimate Details

Estimator: Gary Haverly

ADD ALTERNATE #1: 6 PICNIC TABLES

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total		
01 - General Requirements											
1	01-31-13-90-0020	Performance bond, for buildings, minimum	Job	4,728.90	0.00	0.00	0.00	0.6000%	\$28.37		
2	01-31-13-90-0100	Performance bond, for buildings, minimum	Job	4,728.90	0.00	0.00	0.00	2.5000%	\$118.22		
01 - General Requirements Total									\$146.59		
Alternates											
3	12-56-51-10-8520	Picnic tables, expanded metal plastic-coated, 8' ADA accessible picnic table	Ea.	2	CARP	6.00	680.00	36.50	0.00	\$716.50	\$4,299.00
Alternates Total									\$4,299.00		

Estimate Grand Total 4,822.43



BUILDING CORPORATION

First Choice for Facilities Renovation & Construction

Estimate Details
Labor - Material - Equipment
Gary Haverly
Alpha Building Corporation
City of San Antonio - COSA - Job Order Contract

Estimator: Gary Haverly

ADD ALTERNATE #2: 6 PARK BENCHES

Division Summary (MF04)

01 - General Requirements	\$132.07	23 - Heating, Ventilating, and Air-Conditioning (HVAC)	
02 - Existing Conditions		26 - Electrical	
03 - Concrete		27 - Communications	
04 - Masonry		28 - Electronic Safety and Security	
05 - Metals		31 - Earthwork	
06 - Wood, Plastics, and Composites		32 - Exterior Improvements	
07 - Thermal and Moisture Protection		33 - Utilities	
08 - Openings		34 - Transportation	
09 - Finishes		35 - Waterway and Marine Transportation	
10 - Specialties		41 - Material Processing and Handling Equipment	
11 - Equipment		44 - Pollution Control Equipment	
12 - Furnishings		48 - Electric Power Generation	\$3,873.00
13 - Special Construction		Alternates	
14 - Conveying Equipment		Trades	
21 - Fire Suppression		Assemblies	
22 - Plumbing		MF04 Bare Total (Without totalling components)	\$4,005.07
Totalling Components			
07 - COSA JOC Standard (-20.4000%)		07 - Non-Priced Line Items Multiplier (10.0000%)	\$387.30
07 - Priced Line Items	\$132.07	02 - 07 RS Means CCI San Antonio, TX 1 (-15.7965%)	\$120.86
07 - Non-Priced Line Items	\$3,873.00		
Material, Labor, and Equipment Totals (No Totalling Components)			
Bare Cost			

Material: \$3,480.00
Labor: \$393.00
Equipment: \$0.00
Other: \$132.07
Laborhours: 0.00

Grand Total \$4,344.57

Estimate Details

Estimator: Gary Haverly

ADD ALTERNATE #2 6 PARK BENCHES

Item	Description	UM	Crew	Quantity	Material	Labor	Equipment	Unit Cost	Total		
01 - General Requirements											
1	01-31-13-90-0020	Performance bond, for buildings, minimum	Job	4,260.30	0.00	0.00	0.00	0.6000%	\$25.56		
2	01-31-13-90-0100	Performance bond, for buildings, minimum	Job	4,260.30	0.00	0.00	0.00	2.5000%	\$106.51		
01 - General Requirements Total									\$132.07		
Alternates											
3	12-93-43-13-0400	Site seating, plastic-coated metal bench, with back, one piece, 6' long	Ea.	2	CLAB	6.00	580.00	65.50	0.00	\$645.50	\$3,873.00
Alternates Total									\$3,873.00		

Estimate Grand Total **4,344.57**